

ROBERT W. NICKLES, General Manager ROGER P. FOX, Station Director

13 March 1951

Mr. Norman L. Maguire W5NXF 434 North Maple Albuquerque. N.M.

Dear Mr. Maguire:

Thank you for your letter of March 1st reporting the reception that date of KFAL in Albuquerque.

Your report of reception is confirmed by our station log as 559:30 PM (CST) to approximately 605:15 PM.

We are indeed interested in this report, for reception over such distances is unusual. Apparently the skywave signal was building up considerably as sunset approached. This so far is our maximum DX reported on daytime operation.

KFAL operates with 250 watts into a quarter-wave guyed vertical, using a quarter-wave ground system. The transmitter is a Western Electric 310-B using six 2420 tubes in the final stage.

Cordially yours

R. W. Nickles

(ex-W9EPX)