



April 4, 1985

Mr. Bill Nittler
P.O. Box 824
Mancos, Co. 81328

Dear Sir;

This is to confirm the reception of KFQX on the evening of March 19, 1985 from 6:40 to 7:25 P.M. . KFQX operates with 5Kw. non-directional daytime and 1Kw. directional nighttime with a three tower in line directional array oriented Northeast to Southwest, Each tower is 300' tall. Thank you for your interest in KFQX.

Sincerely,

A handwritten signature in cursive script that reads 'Glenn Welch'.

Glenn Welch
Chief Engineer

