

# WIGA

**AM**

970 KC

**FM**

103.7 MC

**TV**

CH 15

SERVING THE VAST AUDIENCE OF NORTHEASTERN OHIO &amp; NORTHWESTERN PENNSYLVANIA

JEFFERSON ROAD  
ASHTABULA, OHIO

*Mr. David Thomas  
Proctorville, Ohio*

*Jan 3, 1955*

**AM Operation:**

Consists of RCA 5kw transmitter, 5kw daytime, 1kw nighttime, Four tower array, 250 feet, Quarter wave. Hours of operation - daily from 7:00 A.M. to 11:15 P.M. except Sundays, from 8:15 A.M. to 11:15 P.M.

**FM Operation:**

Consists of REL 10kw transmitter, operated at 7.6kw. RCA Pylon 4 sectional steel antenna, with the gain of 6, - 330 feet high. ERP. 41,000 watts. Hours of operation daily from 12:00 P.M. to 11:15 P.M.

**TV Operation:**

RCA 1kw UHF transmitter on Channel 15, RCA antenna with the gain of 24. Video ERP 19,200 watts - Audio ERP 12,000 watts. RCA live camera, RCA Film chain and Slide projector. Monoscope camera. Hours of operation test pattern from 2:00 P.M. to 6:00 P.M. daily except Sundays and Holidays. Test pattern Sundays and Holidays from 5:00 P.M. to 6:00 P.M. Program service from 6:00 P.M. to 9:00 P.M. daily except Saturdays and Sundays. Saturday and Sunday program service from 6:00 P.M. to 10:00 P.M. Power increase with RCA 12.5kw amplifier expected in the fall.

Thank you very much for reception report, *on FM.*

Sincerely yours,

WICA, Inc.

*Frank N. Bernato*

Frank N. Bernato,  
Chief Engineer